

Payload Onboarding Process:

To initiate the onboarding process of the client payload, EXOS shall begin as follows.

#1: Payload Guide Review

The client will review the EXOS Payload User's Guide (PUG) linked at www.exosaero.com/pug. The client will be thoroughly studied in Chapter 4 of the PUG as follows:

- Section 4.1 - Payload Bay dimensions & environment.
- Section 4.2 - G-Force and Vibration environment of flight.

It is recommended that the client also read the remainder of Chapter 4. Likewise, the client shall study Chapter 5 to understand the EXOS payload integration process.

#2: Letter of Intent To Fly

The client shall submit a letter of intent for a flight slot onboard the chosen flight of EXOS Aerospace's SARGE vehicle. The client will note in the letter the preliminary agreements on EXOS flight.

#3: Technical Description of Payload

Client shall submit a technical report on the design of the payload:

- Engineering drawings or pictures (minimum) of the assembled payload.
- 3 Spreadsheets preferred to include:
    - X, Y, Z dimensions and locations and orientations of individual components of the payload.
    - Weights and center of gravity of the entire assembled paylaod.
    - Overall Maximum Power requirement of the device, including Amps and Volts.

- Materials Description:
    - Amount of mass of materials that are radioactive and/or biological.
    - Materials Safety Data Sheets for any materials in the satellite, especially radioactive and biological payloads.

The client shall also fill out the payload questionnaire as well ('EXOS Payload Data Sheet').

Once EXOS has received the technical description of the payload and EXOS Engineering Team has reviewed the documents, Exos will initiate a Launch and Payload Integration Services Agreement. Once signed and Milestone 1a completed (including receipt of initial payment), client and EXOS shall hold a payload meeting to continue the process through to acceptance, delivery, and integration of client payload.

#4: Payloading Process Preview

For the payload to efficiently pass the payload review and integration process before the client's selected flight date, the client shall plan to deliver the payload to EXOS's Greenville, TX facility 45 days before launch.

Before the client delivers the payload, it is recommended that the client execute a G-shock and vibration mechanical load and thermal test on the payload to assure that it can pass an EXOS payload qualification test. References to the G-shock and vibration loads and spaceflight temperature ranges are in the PUG, Chapter 4, Sections 4.1 & 4.2 (link).

#5: Reciprocal Cross-Waiver of Claims (FAA Payload Approval)

Under the FAA's reciprocal waiver of claims requirements (14 CFR 440.17), each customer must enter into a reciprocal waiver of claims with EXOS (and, for licensed activities in which the United States is involved, with the FAA) under which each party waives claims against the others and assumes responsibility for its own property damage and its own employees' injuries resulting from the licensed activity, regardless of fault. The client must also extend the waiver to its own contractors, subcontractors and customers involved in the launch.

The client shall deliver the ORIGINAL, WET-SIGNED cross-waiver of claims to EXOS (299 FM 1903, Greenville, TX 75402) no later than 90 days before the scheduled launch date (L-90). Electronic or e-signed copies do not satisfy this step.

EXOS compiles the executed cross-waivers from every customer on the flight and submits them to the FAA as part of the payload review and approval for that launch. The waiver uses a form acceptable to the FAA Administrator (see FAA Advisory Circular AC 440.17-1).

A payload will not be accepted for integration or flown until its executed cross-waiver is on file at EXOS and has been submitted to the FAA. EXOS tracks this for every order in Mission Control (Payload Orders: 'FAA cross-waiver of claims', due L-90).

Revision History

Rev3 — 2020-05-28 — Prior release.

Rev4 — 2026-10-08 — APPROVED 2026-10-09 by John Quinn, Cofounder & CEO: added Step #5, Reciprocal Cross-Waiver of Claims (wet-signed original at EXOS by L-90; EXOS submits all waivers to the FAA for payload approval).

